

**CITY OF DAHLONEGA  
INVITATION TO BID**

**SIDEWALK CONSTRUCTION ON WIMPY MILL ROAD  
OSS PROJECT #2017-003**

**ADDENDUM NUMBER 1**

This addendum provides answers to questions submitted by potential bidders.

1. What do you want to do with this area? a flume? please clarify.



*The sidewalk in this location is expected to be constructed in a manner allowing concentrated storm water and sheet flow to cross the sidewalk into the neighboring ditch. Sidewalk grades should remain consistent with Americans with Disabilities Act requirements. Additional concrete shall be installed on the south side of the sidewalk directing concentrated flows into the existing ditch.*

2. How many ADA ramps are to be installed?  
*All crossings shall be ADA compliant. Ramps must be held to less than the maximum ADA compliant grades. At any and all crossings of streets and driveways, tactile warning devices (AKA, truncated domes) shall be installed. Please use the "Clay Red" variety.*
3. Are the sidewalks across street intersections to be concrete or thermo-plastic painted?  
*Across the existing concrete driveways, thermoplastic is acceptable. Removal and replacement of concrete is not necessary at these locations. However, at the following locations, the concrete sidewalk shall extend across the secondary street/driveway: 448 Wimpy Mill Road (along the entire length of asphalt), Silver Ridge and Darby Lane.*
4. Is there a pipe to be installed at the end of curb and gutter at Roberta Green's Apartments and what size?  
*Please see response to Question 1.*